



Republic of the Philippines  
**ZAMBOANGA CITY WATER DISTRICT**  
Pilar Street, Zamboanga City

**SUPPLEMENTAL/BID BULLETIN**  
**ADDENDUM NO. 01 – 24-0121**  
**Series of 2024**

This SUPPLEMENTAL BID BULLETIN is issued to clarify, modify or amend items in the issued Bidding Documents for the below subject procurement in view of the Pre-Bid Conference last July 02, 2024, at the BAC Room, 3<sup>rd</sup> Floor, ZCWD Bldg., Pilar Street, Zamboanga City and via Video Conferencing.

PR No.	Item Description	Issues/Amendments/Updates /Clarifications to the Bidding Documents
24-0121	Proposed Well Exploration, Testing and Development at Mercedes	<ul style="list-style-type: none"><li>• The Stick Up Pipe or Riser Pipe shall be 300mm dia. Steel Pipe spirally welded per AWWA C200 which may connect/joint through flange, butt strap welded or threaded and shall have a minimum thickness of 4.7mm;</li><li>• <b>Temporary Site Facility</b> The Contractor shall provide and maintain at least one temporary field office at the project site dedicated for Contractor's personnel &amp; ZCWD Field Engineer, the size of the temporary facility shall be at least as reflected in the detailed plan, however, the Contractor may opt to construct larger facility without additional cost to the ZCWD. Further, the Contractor is not required to construct another temporary field office for the ZCWD field engineer.</li><li>• The 20-HP submersible pump, under SPL-4t, shall have the following minimum specifications:<ul style="list-style-type: none"><li>• 3" NPT Riser Pipe Connection</li><li>• Head 80m-89.9m</li><li>• Q (flow) = 35 - 37 cu.m./hr.</li><li>• Bowl, Impellers &amp; Shafting all in stainless;</li><li>• Complete with cable guard,</li><li>• Suction strainer, Built-in check valve;</li><li>• 8 Stages w/ complete Stainless Steel Bolt w/ lock washer;</li></ul></li></ul>

		<ul style="list-style-type: none"><li>• 3,400-3500 rpm</li><li>• 3-Phase, 230VAC, 60Hz</li><li>• With Motor Controls</li></ul> <ul style="list-style-type: none"><li>• Under the <i>SPL-4t Well Testing (72 hours)</i>, the provision for rental of submersible pump and genset equipment are included in the pay item, should the Contractor opt to use the newly supplied <i>20-HP Submersible Pump/Motor w/ motor controls</i> in the conduct of the Well Testing, the equipment rental component of the submersible pump/motor under the <i>SPL-4t Well Testing</i> shall be deducted from the Contractor otherwise it will remain as pay item.</li> <li>• Attached herewith are the <i>Technical Specifications</i> (clear copy) and the amended description on the Bill of Quantities which shall be followed by the Bidders in this procurement &amp; implementation;</li></ul>
--	--	---




**BILL OF QUANTITIES**

**PROPOSED WELL EXPLORATION, TESTING AND DEVELOPMENT AT MERCEDES**

ITEM NO.	DESCRIPTION	QUANTITY	UNIT	UNIT COST (W/ OCM, PROFIT & VAT)	TOTAL
SPL - 1	MOBILIZATION/DEMOBILIZATION (UP TO 1% OF ESTIMATED DIRECT COST)	1.00	LOT		
SPL - 2	CONSTRUCTION SAFETY & HEALTH PROGRAM	1.00	LOT		
SPL - 3	CONSTRUCTION OF PROJECT BILLBOARDS/ SIGNAGES	1.00	LOT		
<b>Well Exploration, Testing and Development at Mercedes</b>					
SPL - 4a	SITE PREPARATION, CONSTRUCTION OF TEMPORARY FACILITY AND SETTING-UP OF EQUIPMENT	1.00	LOT		
SPL - 4b	DRILLING OF PILOT HOLE	77.40	METERS		
SPL - 4c	BOREHOLE LOGGING OF PILOT HOLE	1.00	LOT		
SPL - 4d	REAMING TO 400mmØ BOREHOLE	77.40	METERS		
SPL - 4e	FURNISHING OF 250mmØ BLANK CASING	55.18	METERS		
SPL - 4f	FURNISHING OF 250mmØ SCREEN	23.22	METERS		
SPL - 4g	FURNISHING/FABRICATION OF 250MMØ END CAP	1.00	PC.		
SPL - 4h	INSTALLATION OF BLANK CASING, SCREEN AND END CAP	78.40	METERS		
SPL - 4i	FURNISHING AND INSTALLATION OF CASING CENTRALIZERS	6.45	PCS.		
SPL - 4j	FURNISHING AND INSTALLATION OF GRAVEL PACKING AT ANNULUS AROUND CASINGS AND SCREENS	62.40	METERS		
SPL - 4k	DE-FLOCCULATION OF DRILLING MUD WITH POLYPHOSPHATE SOLUTION	1.00	LOT		
SPL - 4l	DEVELOPMENT BY WATER JETTING	12.00	HOUR		
SPL - 4m	DEVELOPMENT BY SURGING AND BAILING	12.00	HOUR		
SPL - 4n	DEVELOPMENT BY AIRLIFTING	12.00	HOUR		
SPL - 4o	STEP DRAWDOWN PUMPING TEST	1.00	LOT		
SPL - 4p	WELL TESTING (72 hours Constant Rate Discharge Test)	72.00	HOUR		
SPL - 4q	CEMENT GROUTING OF ANNULUS	15.00	METERS		
SPL - 4r	WELL DISINFECTION AND CLEANING	1.00	LOT		
SPL - 4s	FURNISHING AND INSTALLATION OF 300 MM STEEL PIPE AS STICK UP PIPE	1.00	LOT		
SPL - 4t	SUPPLY, INSTALLATION, TESTING & COMMISSIONING OF ONE (1) UNIT 20 HP SUBMERSIBLE MOTOR & PUMP, 3" INLET AND OUTLET SUCTION W/ COMPLETE ACCESSORIES <b>INCLUDING MOTOR CONTROLS</b>	1.00	ASSY.		
SPL - 4u	WELL COMPLETION, FURNISHING & INSTALLATION OF GRAVEL FILL PIPE 50MMØ WITH SCREW CAP AND FURNISHING AND INSTALLATION OF WATER LEVEL 38MMØ SOUNDING TUBE	1.00	LOT		
<b>TOTAL BID AMOUNT</b>					

Prepared & Submitted by:

For guidance and information of all concerned.

  
**ATTY. VINCENT F. FERNANDEZ**  
Chairperson  
Bids and Awards Committee

Posting date: July 08, 2024.  
Posted in the Phil-GEPS, ZCWD Website & Bid Bulletin