PURCHASE ORDER (PO)

Supplier	: GSFERROLINO CONSTRUCTION & SUPPLY	P.O. No.	: 14845
Address	: Kidapawan, North Cotabato	Date	: March 01, 2024
Email address	:	Mode of Procurement	: Emergency Cases (Sec 53.2)
Telephone No.	: 064 523-0052/288-5879		
TIN	:		

Gentlemen/Ladies :
Please furnish this Office the following articles subject to the terms and conditions contained herein.

Place of Delivery	: Property Section, ZCWD Motorpool, Pasonanca, Z.C.	Delivery Term	: 14-CD
Date of Delivery	:	Payment Term	:

STOCK NO.	ITEM #	DESCRIPTION	QTY.	UOM	UNIT COST	AMOUNT
1060599003	1	Supply of Brand New: **Grundfos Submersible Pump Model SP30-8** 15HP Submersible Pump/Motor **3"npt 6" 50/60** Specifications: (a) 15Hp. 3-phase. 230VAC. 60Hz. 53.8Amps. SF: 1.15. **Franklin** 60.6Amax, 3450rpm **Electric Motor** (b) 138mm diameter. Complete with motor leads. (c) with 1 roll Elec'l & Rubber Tape & 2 packs splicing kit. Submersible Pump (intended for 15hp submersible motor) (a) 3" NPT or its equiv. Riser Pipe Connection, Head: 80m-89.9m (b) Q: 35 m³/hr - 37m³/hr capacity (c) All in Stainless Steel construction; Bowl, implellers & Shafting, (d) Complete w/ cable guard, suction strainer (e) Built-in check valve. Eight (8) stages w/ four (4) 12mmØx 38mm SS bolt with lock washer, 3450rpm	2	sets	Php 300,500.00	Php 601,000.00
	2	7.5Hp Multi-stage Vertical Pump (1 phase) **Grundfos Centrifugal** See attached Specifications: **Pump model CR 10-7 A-GJ-A-E-HQQE** (a) Vertical, Non-self priming, multi-stage, in-line pump. (b) Impellers & intermediate chambers are made of Stainless Steel (c) Pump head and base are made of Cast Iron. (d) The shaft seal has assembly length according to EN 12756. (e) Pipework connection is via ANSI flanges (f) Pipe connection: 2 Inches (g) Nominal Capacity: 12m³/hr - 14m³/hr (h) Nominal Speed: 3500rpm - 3600rpm (i) Nominal Head: 65m - 70m (j) No. of Stages: 7 (k) Motor Rating: 7.5Hp, Single Phase 200V-230V, 60HZ, 3450rpm, S.F. 1.15, end: TEFC xxxxxxxxxxxxxxxxxxxxxxxxxxxxxx nothing follows xxxxxxxxxxxxxxxxxxxxxxxxxxxxxx (Details Attached)	1	set	Php 216,500.00	Php 216,500.00
		Purpose: For installation of electro-mechanical equipment @ Ayala 2 & Tulungatung 1 Production Well and spare pump for Cabatangan Booster Station.				
		Note: Delivery of Items/Units must be accompanied with Photo Copy of P.O., Charge Invoice or Credit Invoice for reference.				
		Note: Warranty Period: 1 Year for Non-Expendable supplies after acceptance by the procuring entity.				
		Price Validity: 120 CD Payment Terms: No COD				
Total Amount in Words		EIGHT HUNDRED SEVENTEEN THOUSAND FIVE HUNDRED PESOS				Php 817,500.00

In case of failure to make the full delivery within the time specified above, a penalty of one-tenth (1/10) of one (1%) percent for every day of delay shall be imposed.

Very truly yours,

REYNALDO R. CABILIN, MPA
Acting General Manager

Conforme :

GENEVA S. FERROLINO, CE
Signature over Printed name of Supplier

03-19-2024
Date

Funds Available :

SHERWIN B. ABRIAM

ALOBS No. :
Amount :
P.R. No. 24-0001